

# TOWN OF NORTH HAVEN

MEMORIAL TOWN HALL / 18 CHURCH STREET

NORTH HAVEN, CONNECTICUT 06473



REPLY TO:

## PLANNING AND ZONING COMMENTS

for 8 NOVEMBER 2021

Tel. (203) 239-5321

Fax (203) 234-2130

#P21-29

48 GILES AVENUE

IG-80

#P21-29A

(MAP 28, LOT 13)

**LOCUST REALTY ASSOCIATES, LLC, APPLICANT & OWNER  
SITE PLAN & CAM**

### Review Comments:


1. These applications are intended to permit the construction of a new 14,000 square feet, single story building to be used as a trucking facility. Additionally, approval is being sought for the outdoor storage of vehicles, construction equipment, construction material and asphalt millings.
2. The Zoning Board of Appeals previously approved front and rear yard setback variances for this property, (#10-05 & #08-03 respectively).
3. A Cease and Desist Order was issued on September 21, 2020 for the unpermitted outdoor storage of school buses. This proposed site plan is requesting an approval to cure this violation.
4. The CAM approval is required because the site lies within the Coastal Boundary.
5. The drawings indicate that this work would be completed in two (2) phases. Clarification should be provided as to exactly what work is associated with each phase.

### Recommended Conditions of Approval, if granted:

1. Submit revised plans which include:
  - a. A note on the title sheet indicating “#P21-29, Site Plan and #P21-29A, CAM”.
  - b. Elimination of note indicating ZBA variance granted on 1/7/08 for front yard setback.
  - c. Revised Zoning information table to indicate rear yard setback variance to allow 40’, not 40.5’. Also, reverse notes relative to “buffer strip” and “setbacks”.
  - d. Landscape Plan revised to provide required 30’ wide buffer strip along all residential district boundary lines with evergreen plantings, in accordance with Section 8.7.8.2(2).
  - e. Dumpster pad with screened, landscaped enclosure.


- f. 8' wide landscaped islands with minimum 2" caliper tree at ends of all rows of parking.
  - g. Proposed type, design, mounting height, location, direction, power and timing of all outdoor lighting.
  - h. Clear delineation of all areas to be used for outdoor storage of materials, equipment and/or vehicles.
2. Soil and erosion controls must be inspected by the Zoning Enforcement Officer before work may commence.
  3. The property owner, and/or his/her agents, must maintain (repair/replace) when necessary, the siltation control until all development activity is completed and all disturbed areas are permanently stabilized.
  4. Any proposed signage or fencing will require the filing of applications with the Zoning Enforcement Officer.
  5. Submit an as-built plan prior to bond release.
  6. Post bond, as required.

Submitted by,



Alan A. Fredricksen  
Land Use Administrator  
#P21-29 & #P21-29A  
AAF/llc





# TOWN OF NORTH HAVEN

MEMORIAL TOWN HALL / 18 CHURCH STREET  
NORTH HAVEN, CONNECTICUT 06473



REPLY TO: Engineering

Tel. (203) 239-5321  
Fax (203) 234-2130

## PLANNING AND ZONING

**Date of Meeting: 11/08/2021**

Dev: New Building/Site Plan  
Loc: 48 Giles Avenue  
File: P21-29

\*\*\*\*\*

### Comments:

1. The NRCS soils report included within the Applicant's Stormwater Management Report shows underlying soils in the existing site condition made up of a mix of Soil Groups A and B. It is unclear then why the existing RCN for the existing lawn areas was based on a Soil Group C. Changing this to Soil Group B would result in a change in the existing RCN from 80 to 70. Provide justification for utilizing a Group C soil, or revise the study analysis to reflect soil groups as shown in the NRCS report.
2. It is standard practice to incorporate a gross particle separator device immediately upstream of the underground stormwater infiltration galleries in order to reduce sediment loading on the system, and reduce the need for sediment removal.
3. A written long-term post construction inspection and maintenance plan shall be provided incorporating all components of the stormwater management system. Regular inspection and maintenance of the stormwater management systems is critical in assuring their effective long-term use.
4. It does not appear that the existing on-site storage of buses and construction equipment was ever approved by the Commission. These areas are referenced as vehicle parking and storage on the currently submitted site plan. It is unclear if the applicant is seeking approval for these outside storage uses, or just noting their existence. If approval is being sought with this application, the Commission must consider if a surface consisting of compacted asphalt millings is an appropriate surface for maneuvering and storing vehicles and heavy equipment.
5. If the vehicle storage use is proposed to remain, stormwater management features must be expanded to include these areas as well. Placement of millings in this existing lot was not permitted by the Town, and represents a significant increase in impervious area over the gravel lot which was present prior to the last site plan approval in 2010. If the current vehicle storage use is to be discontinued, the millings shall be removed, topsoil placed, and soils stabilized with a stand of grass or other approved ground cover.
6. The southerly sections of the site are shown on the site plan with an existing surface cover of gravel. This must be revised to reflect the asphalt millings that are currently in place at this location.
7. Landscape islands with trees are required at all ends of all parking rows.
8. The Applicant must coordinate the proposed drainage improvements with CT DOT. Drainage from the existing and proposed sites discharges directly onto the I-91 ROW. Modifications to the drainage system may require approval by CT DOT.

BOND RECOMMENDATION: \$21,500

DATE REVIEWED 10/27/2021

TOWN ENGINEER: J. Andrew Bevilacqua, P.E. *AB*